

SANITARY MANHOLE

STD. DRW. NO. 16.44.060.J DATE: 5-2-02





SECTION A-A

- PROVIDDE CA-6, COMPACTED OR CA-7 AGGREGATE BACKFILL AROUND MANHOLE TO SUBGRADE ELEVATION IN PAVED AREAS.
- 2. CONCRETE FILLETS SHALL BE MADE WITH ADDITIONAL MORTAR TO PROVIDE A SMOOTH TRANSITION BETWEEN THE CASTING AND ADJUSTING RINGS (OR TOP OF STRUCTURE)
- 3. INSTALL MANHOLE IN ACCORDANCE WITH ASTM C891.
- 4. MORTAR SHALL NOT BE USED TO DRESS UP INTERIOR JOINTS.
- NEENAH FOUNDRY C.CAT.* R-1712-B.E.JORDAN IRON WORKS CO.CAT.*
 1051-3 (EXTRA HEAVY DUTY COVER OR APPROVED EQUAL IN PAYED AREAS
 IN OTHER AREAS USE R-1772-B (NEENAH), 1022-1 (MED.COVER) (E.JORDAN),
 IN NON-PAYED AREAS SET FRAME IN BUTYL ROPE.
- 6. WHEN MANHOLE IS 12' OR LESS,T * 6" WHEN MANHOLE DEPTH IS OVER 12',T * 10"

CITY OF ST. CHARLES